



### NATIONAL INSTITUTE FOR RESEARCH, DEVELOPMENT AND TESTING ELECTRICAL ENGINEERING

# ICMET CRAIOVA

High Voltage Division - HVD
High Voltage Testing and Electomagnetic Compatibility Laboratory
LIT - CEM



Bvd. Decebal No.118A, 200746 Craiova, ROMÂNIA Phone: + 40 0351 402425, 404888; Fax: + 40 0351 404890 www.icmet.ro, e-mail: market@icmet.ro

# TEST REPORT No. 44305 / 14.07.2014

1. CUSTOMER: FOREND Elektrik Malz. Ve Dis Tic. A.S.

Address: Halaskargazi cad. No. 141 K: 4/7 Osmanbey – Sisli – Istanbul TURKEY

2. MANUFACTURER: FOREND Elektrik Malz. Ve Dis Tic. A.S.

Address: Halaskargazi cad. No. 141 K: 4/7 Osmanbey – Sisli – Istanbul TURKEY

3. TESTED PRODUCT: Early Streamer Emission Lightning Conductor (E.S.E.L.C.) type FOREND EU-M
Serial no.: prototype

4. REFERENCE STANDARD: NFC 17-102: 2011 Annex C; UNE 21186: 2011, Annex C

5. TEST PERFORMED: Early streamer emission tests

6. TEST DATE: 11.07.2014

7. TEST RESULTS: There are presented the determined results.

8. The report contains: 14 pages

9. The test report is edited in 4 copies, copy no.1 remain in laboratory and copies 2, 3 and 4 are sent to the customer.

**HEAD OF HV DIVISION** 

Eng. MIHAI George

HEAD OF LABORATORY

Eng. BADEA Ion

1. Results refer to the tested product only.

2. Publication or reproduction of the contents of this report in any other form unless its complete photocopying is not allowed without writing approval of Division to which laboratory belongs.

3. All signatures of the present report are original ones.

© ICMET Craiova 2014

## **TEST REPORT No. 44305**



HVD

Content		page
	Identification of the test product	3
>	Tests program	3
>	Responsible for tests	3
	Opinions and interpretation (if necessary)	3
	Present at the tests	3
	Tested material	4
	Type of tests	4
	Specification	3
	Test equipment	4
	Test circuit	4
	Mounting arrangement	5
	Test procedure	5
	Test on simple road lightning conductor (S.R.L.C.)	6
	Test on early streamer emission lightning conductor (E.S.E.L.C.) type FOREND EU-M	7
	Table with measuring results on S.R.L.C.	8
	Table with measuring results on E.S.E.L.C. type FOREND EU-M	9
	Graphic determination of the E.S.E.L.C. type FOREND EU-M efficiency	10
	Photos	11
	Test circuit diagram	12
	Test set-up on early streamer	13
	Drawing	14



#### 1. IDENTIFICATION OF THE TEST PRODUCT:

Type: FOREND EU-M Early Streamer Emission Lightning Conductor

Serial / year: prototype / 2014

Technical Specification / Drawing: - / see page 14

**Contract client:** 8236 / 23.06.2014

**Internal test order:** 22451 / 24.06.2014

Product receiving date: 20.06.2014

Product condition at receiving: New

2. TEST PROGRAM: Early streamer emission tests

3. RESPONSIBLE FOR TEST: Eng. Mircea BORUZ

- 4. OPINIONS AND INTERPRETATION (IF NECESSARY):
- 5. PRESENT AT THE TEST:



HVD

#### 1. Tested material

Early Streamer Emission Lightning Conductor type FOREND EU-M

See photo on page 11 and drawing on page 13.

#### 2. Type of tests

A switching impulse wave having negative polarity and a DC voltage also of negative polarity were applied on the upper metallic plane.

#### 3. Specification

NFC 17-102 : 2011 Annex C UNE 21186 : 2011, Annex C

#### 4. Test equipment

Laboratory inner dimensions: 48 m x 32 m x 27 m (height)

Altitude: 100 m above see level

4200 kV High Voltage Impulse Generator type SPF 340; 340 kWs, TUR

Dresden - Germany

1000 kV Rectifier cascade type GS 1000 / 30; 30 mA; TUR Dresden – Germany

1400 kV Damped capacitive divider, ICMET Craiova, Romania;

TR – AS Transient – Recorder, Dr. Strauss System Electronik, GmbH- Germany

Digital multimeter Keithley, serial no. 1070037 - USA.

#### 5. Test circuit

See the test circuit diagram on page 12.

The measuring system consists of:

- 1400 kV damped capacitive divider, calibration certificate DKD-K-18701 / 12.2011, no. 278;
- Transient recorder, TR AS 100 10 / 4, calibration certificate D- K-15205-01-00, no. 633 / 2012.05;
- DC measuring system that consists of DC resistive divider and digital multimeter type Keithley, calibration certificate DKD K 18701, no. 211 / 2010-06.

The expanded uncertainties of the measuring systems are inside the limits prescribed by IEC 60060 - 2 / 2010 for SI Approved Measuring Systems (3 % for peak values and 10 % for time parameters).



#### 6. Mounting arrangement

See the test set up on page See photo on the pages 11

The tested lightning conductor was set on a 5 x 5 m grounded metallic plane and connected to ground.

A square metallic plane with dimensions: 4.5 m / 4.5 m / 0.2 m having the edges rounded, was suspended above the lightning conductor and connected to the high voltage source.

#### 7. Test procedure

The DC polarization voltage was applied on an upper square metallic plane.

The negative impulse wave was adjusted in order to obtain a flashover.

The height of the lightning conductor (h) and the distance between the ground and the square plane (H) were measured at the beginning of each test.

The atmospheric conditions were taken at the begging, at the middle and at the end of each test. The peak value (Up) of the impulses and the triggering time (T<sub>B</sub>) were recorded for each impulse.

The early streamer emission lightning conductor (E.S.E.L.C.) is to be compared with a simple rod lightning conductor (SRLC).

Tests were performed in the same conditions and configuration for each lightning conductor: E.S.E.L.C. and S.R.L.C.

First, there were applied 50 impulses on the S.R.L.C. and after that 50 more impulses were applied on the E.S.E.L.C. type FOREND EU-M.

Height of lightning conductor (h) adjusted to: 1182 mm Distance between ground / square plane (H) adjusted to: 2450 mm h / H: 0.482 Polarization voltage: 54.2 kV Peak time / Rise time of the full wave:  $291 \, \mu s / 369 \, \mu s$ 

Time interval between consecutive impulses: 2 min



#### 8. TEST ON S.R.L.C.

8.1. Test date: 10.07.2014

#### 8.2. Atmospheric conditions

BEFORE TEST	p = 1002  mb $t = 22  ^{0}\text{C}$ hr = 62.5  %
MIDDLE OF THE TEST	p = 1002  mb $t = 22  ^{0}\text{C}$ hr = 62  %
END OF THE TEST	p = 1002  mb $t = 22  ^{0}\text{C}$ hr = 61  %

#### 8.3. Results

See tables on page 8

Number of significant impulses:

50

The average value of significant break-down times ( $T_B$ ) calculated from the experimental results is  $T_{SRLC}$  = 171.43  $\mu s$  with a standard deviation  $\sigma_{SRLC}$  = 19.36 %.

By transferring  $T_{SRLC}$  on the reference waveform it was obtained  $T'_{SRLC} = 211.21 \mu s$ 

See curves on page 10



#### 9. TEST ON E.S.E.L.C. type: FOREND EU-M

9.1. Reception date: 20.06.2014

9.2. Test date: 10.07.2014

#### 9.3. Atmospheric conditions

BEFORE TEST	p = 1002  mb $t = 22  ^{0}\text{C}$ hr = 60.6  %	
MIDDLE OF THE TEST	p = 1002  mb $t = 22  {}^{0}\text{C}$ hr = 60  %	
END OF THE TEST	p= 1002 mb t = 22.3 °C hr = 60 %	

#### 9.4. Results

See tables on page 9

Number of significant impulses:

50

The average value of significant break-down times ( $T_B$ ) calculated from the experimental results is  $T_{ESELC} = 130.11 \,\mu s$  with a standard deviation  $\sigma_{ESELC} = 8.51 \,\%$ .

By transferring  $T_{ESELC}$  on the reference waveform it was obtained  $T'_{ESELC} = 156.73 \mu s$ 

See curves on page 10

Measuring uncertainty for  $\Delta T$  is 5.7 %.

The uncertainty stated is expanded uncertainty obtained by multiplying the standard uncertainty by the coverage factor k = 2. The value of measurand lies within the assigned range of values with probability of 95 %.

Triggering advance: 
$$\Delta T = T'_{SRLC} - T'_{ESELC} = 211.21 - 156.73 = 54.48 \ \mu s \pm 3.11 \ \mu s$$

The tested lightning conductor is an E.S.E.A.T. (early streamer emission air terminal) because it fulfils the following conditions (according to NFC 17-102 / 2011, Annex C, clause C.3.5.2.5):

- $T_{ESELC} < T_{SRLC}$  (130.11 < 171.43);
- $\sigma_{\text{ESELC}} < 0.8 \ \sigma_{\text{SRLC}} \ (8.51 < 0.8 \cdot 19.36);$
- $T_{SRLC} T_{ESELC} > 10$  μs.



Test on S.R.L.C.

Impulse no.	T <sub>B</sub> μs	Impulse no.	T <sub>B</sub> μs
1	194,90	41	149,60
2	141,40	42	188,60
3	175,80	43	147,50
4	151,60	44	178,90
5	188,80	45	157,60
6	172,60	46	134,20
7	157,60	47	226,20
8	144,40	48	131,10
9	190,80	49	182,80
10	197,60	50	194,80
11	138,20	30	174,00
12	194,80		
13	295,00		
14	200,50		
15	142,40		
16	178,80		
17	180,20		
18	175,90		
19	203,00		
20	128,40		
21	188,10		
22	135,10		
23	130,30		
24	235,10		
25	128,20		
26	164,60		
27	205,00		
28	166,80		
29	186,60		
30	205,00		
31	184,00		
32	142,30		
33	156,60		
34	189,60		
35	173,80		
36	134,40		
37	128,40		
38	201,00		
39	130,40		
40	142,40		

T<sub>B</sub>: Break-down time




Test on E.S.E.L.C. type: FOREND EU-M

Impulse no.	T <sub>B</sub> μs	Impulse no.	T <sub>B</sub> μs
	110.20		125.00
1	119,20	41	135,90
2	117,20	42	135,90
3 4	131,20	43	135,30
5	134,20	44	139,20
	139,30	45	128,40
6	139,20	46	129,40
7	120,10	47	125,20
8 9	124,20	48	112,80
	117,00	49	109,40
10	121,20	50	116,70
11	118,00		
12	129,00		
13	131,20		
14	141,20		
15 16	142,20 149,80		
17	149,80		
18	142,30		
19	144,30		
20	142,30		
21	128,20		
22	140,20		
23	121,10		
24	117,70		
25	124,00		
26	130,10		
27	137,70		
28	135,60		
29	128,20		
30	147,60		
31	112,10		
32	139,10		
33	135,80		
34	146,30		
35	120,20		
36	120,80		
37	112,50		
38	145,40		
39	116,20		
40	127,30	6	

 $T_B$ : Break-down time



HVD



#### Where:

- On OX axes there is represented time in μs;
- $\bullet$   $\,$  On OY axes there is represented amplitude U /  $U_{\text{peak}}$  in relative units;
- Red line is the experimental waveform;
- Blue line represents the standard waveform.

$$T_{SRLC} = 171.43 \ \mu s$$
 $T'_{SRLC} = 211.21 \ \mu s$ 
 $T_{ESELC} = 130.11 \ \mu s$ 
 $T'_{ESELC} = 156.73 \ \mu s$ 
 $\Delta T = T'_{SRLC} - T'_{ESELC} = 54.48 \ \mu s$ 






Photo 1



Photo 2




Photo 3



Photo 4



#### Test circuit diagram on lightning conductor




- 1 HV Impulse Generator 4.2MV-336kWs 2 S erial protective gap, Φ=250mm 3 Damped resistive-capacitive divider, 1400 kV 4 Test configuration 5 Resistance 2MΩ

- 6 Parallel protective gap, \$\pi = 500 mm 7 Capacitor 4 SnF

- 8 Rectifier cascade GS 1000/30 9 Transient recorder TR-AS 100-10 10 Digital multimeter KETHLEY serial no.1070037



# TEST SET UP ON EARLY STREAMER EMISSION LIGHTNING CONDUCTOR





NUMBER

CONTROL APPROVAL PRODUCER

QUALITY


SIGNATURE

DATE

REVISION NUMBER

MATERIAL: STAINLESS STEEL 316

WEIGHT:



FOREND EU-M

TOLERANCES STATED IN PICTURES: Measure: £ . 0,5...mm, Angle: £ . 1....\*, Surface Roughness: 3.2  $\mu m$  Code F = 01.09.01(e)

UNIT OF MEASURE: mm

DRAWING NO: